## Minimum Test Times for Additional Modern Welding Tanks

## Glasteel II Model GS-13, GS-16 & Glasteel Model GS-19

(Not specifically listed in Table 3, but calculated in accordance with the 01/2012 Modern Welding third-party certified tank testing protocol)

Tank Capacity (gal.)	Tank Diameter (in.)	Modern Test Time (hrs.)
7,500 ( <u>Calculation Sheet</u> )	72	13
19,400 (Calculation Sheet)	126	20
25,000 (Calculation Sheet)	120	22

Revised 3/5/2013